Ref. No.: NSPPL-C/RFP/FY26-27/MHRP/FOB & PGR

Date: 13.11.2026

Project Name: Request for Engagement (RFP) Issued by National Highways InvIT Project Managers Pvt Ltd from Contractors for Construction of Foot Over Bridges (FOB) and Pedestrian Guard Rail (PGR) along from km 130.560 to km 209.120 of Muzaffarnagar-Haridwar Section of NH-334 in the States of Uttar Pradesh & Uttarakhand.

Corrigendum – III

This has reference to the subject RFP, bearing no. NSPPL-C/RFP/FY26-27/MHRP/FOB & PGR, published on 24.10.2026 on NHIT website (https://nhit.co.in/).

1. Clause no. 2 Bid timelines under section – 1 of RFP document stands revised and may be read as under:

Sr. No.	Description of Events	Subsisting Schedule	Revised Schedule
1	Last date and time for submitting Technical & Financial Bid Documents	16 November 2026 up to 11:00 Hour	19 November 2026 up to 16:00 Hour
2	Opening of Technical bids	16 November 2026 at 11:30 Hour.	19 November 2026 at 17:00 Hour.

2. Clause 1. (A) Bill of Quantities for Construction of Foot Over Bridge (FOB) under Annexure B (Financial Proposal) of the Said document is being revised as per attached **"Revised BoQ"** document attached herewith.

Note: Bidders are advised to take note of the above changes/updates made in the RFP while submitting their bids.

Thank you,
For and on behalf of
NHIT Southern Projects Private Limited

Sandeep Khosa
GM Procurement
NWPPL (Unit of NHIT)

Scanned with OKEN Scanner

Revised BoQ - Clause 1. (A) Bill of Quantities for Construction of Foot Over Bridge (FOB) under Annexure B (Financial Proposal)						
S. No.	BoQ Item No.	Description	Unit	Quantity	Unit Rate	Amount in Rs.
				A	B	C = (A x B)
	1	**BILL NO.1 EARTHWORK**				
1	1.01	**Embankment Construction with Material Obtained from Borrow Pits** (Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2)	Cum	140.000		-
		TOTAL FOR BILL NO.1				-
	2	**BILL NO.2 FOOT OVER BRIDGE**				
2	2.01	**Earthwork in excavation** of foundations of structures in all kinds of soils including all leads and lifts complete as per drawings and Technical Specifications Clause 304				
	a)	All types of soils including marshy soil and ordinary rock	Cum	274.469		-
3	2.02	**M15 Grade** Plain Cement Concrete below foundation, footings, etc as levelling course as per drawings, clause 1500, 1700 & 2100 of MORT&H Specification (2001).	Cum	14.013		-
4	2.03	Providing and laying plain/Reinforced cement concrete for foundation and substructure complete as per drawing and technical specifications section 1500,1700,2100 and 2200				-
	a)	**RCC M20**	Cum	55.253		-
	b)	**RCC M30**	Cum	70.275		-
5	2.04	Supplying, fitting and placing HYSD bar reinforcement of Grade Fe 415 complete as per drawings and Technical Specifications Section 1600 (In Foundations)	MT	11.210		-
6	2.05	Providing and laying **chequered cement concrete heavy-duty flooring tiles** of size 300 mm × 300 mm (approximately 1 ft × 1 ft) and 25 mm thick, conforming to IS 13801:2013, of approved colour, shade and pattern, laid over 20 mm thick cement mortar bed 1:4 (1 cement : 4 coarse sand), including cement slurry, jointing with neat cement slurry/pigment matching the shade of tiles, cutting and fitting wherever required, curing, cleaning and finishing complete, including all materials, labour, tools, tackles and incidental works, as per drawings, relevant specifications and as directed by the Engineer-in-Charge.	No's	2,279.705		-
7	2.06	Providing and fixing **pedestrian guard railing** along footpath/at-grade pedestrian area in the vicinity of Foot Over Bridge (FOB), comprising mild steel/galvanized steel posts, horizontal rails and vertical members of approved size and configuration, including excavation, fixing posts in cement concrete foundations, structural steel work, welding, cutting, drilling, nuts, bolts, fasteners and all necessary fittings, surface preparation and approved protective coating/painting, making good the footpath after installation, complete in all respects as per approved drawings, relevant IRC/MoRTH specifications and as directed by the Engineer.	Rmt	150.000		-
8	2.07	Metal Colour Roof Sheet (MS Sheet 2 mm thick)	Sqm	111.900		-
9	2.08	Wire Jali Mesh (2m Height)	Rmt	77.700		-
10	2.09	**Painting on Steel Surfaces** (Providing and applying two coats of ready mix paint of approved brand on steel surface after through cleaning of surface to give an even shade)	Sqm	992.365		-
11	2.10	**Providing structural steel** for super-structure complete as per drawing and technical specifications	MT	80.358		-
12	2.11	**Back filling** in Foundations and return walls with selected granular material of approved quality including all the material, labour equipment carriage etc. all complete as per drawingand Technical Specification Clause 305	Cum	184.112		-
13	2.12	Providing and laying Filter material underneath pitching in slopes complete as per drawing and Technical specification	Cum	63.000		-
14	2.13	Providing and laying Pitching on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and Technical specifications	Cum	126.000		-
15	2.14	6mm thick steel chequered plate for stairs & landings	Sqm	68.600		-
		TOTAL FOR BILL NO.2				-